BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of work: Detailed Estimate for the Work of Improvements to Roads and Drains at Afzal Layout in Ward No. 6 Byatarayanapura Sub Division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	348.90	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2015-16	Cum	288.36	Rupees Two Hundred Eighty Eight and Thirty Six Paise Only
2	594.00	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete - do- 7.5 cms thick Page No. 28/ Item No. 5.31.1/ PWD SR 2015-16	Sqm	663.12	Rupees Six Hundred Sixty Three and Twelve Paise Only
3	20.91	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2015-16	Cum	5070.60	Rupees Five Thousand Seventy and Sixty Paise Only
4	38.61	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2015-16	cum	4135.32	Rupees Four Thousand One Hundred Thirty Five and Thirty Two Paise Only
5	32.18	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2015-16	Sqm	4905.36	Rupees Four Thousand Nine Hundred Five and Thirty Six Paise Only
6	84.14	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16/ Item No. 4.34/ PWD SR 2015-16	Sqm	270.00	Rupees Two Hundred Seventy Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	11.44	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2015-16	cum	5491.80	Rupees Five Thousand Four Hundred Ninety One and Eighty Paise Only
8	71.50	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.1/ PWD SR 2015-16	Sqm	99.36	Rupees Ninety Nine and Thirty Six Paise Only
9	27.13	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2015-16	Cum	6198.12	Rupees Six Thousand One Hundred Ninety Eight and Twelve Paise Only
10	1.36	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46.2/ PWD SR 2015-16	Qtl	69805.80	Rupees Sixty Nine Thousand Eight Hundred Five and Eighty Paise Only
11	360.00	KSRRB M300-53: construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller) MORTH specification Page No. 305.4.3, No. 156/ Item No. 19.60/ PWD SR 2015-16	Cum	311.04	Rupees Three Hundred Eleven and Four Paise Only
12	180.00	KSRRB M400-14.2: Providing, laying, spreading and compacting stone aggregates of specific size to water bound macadam specifications. Including spreading in uniform thickness, hand packing, rolling with 3-whelled steel / vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding materials to fill up the interstices of coarse aggregates, watering and compacting to the required density complete as per specifications. B by mechanical means, MORTH specification No. 404, Crushable type such as moorum or gravel for grading II , No. 166/ Item No. 20.14.1/ PWD SR 2015-16	Cum	1751.76	Rupees One Thousand Seven Hundred Fifty One and Seventy Six Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
13	135.00	KSRRB M400-14.2: Providing, laying, spreading and compacting stone aggregates of specific size to water bound macadam specifications. Including spreading in uniform thickness, hand packing, rolling with 3-whelled steel / vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding materials to fill up the interstices of coarse aggregates, watering and compacting to the required density complete as per specifications. B by mechanical means, MORTH specification No. 404, Crushable type such as moorum or gravel for grading III , No. 166/ Item No. 20.15.3/ PWD SR 2015-16	Cum	1867.32	Rupees One Thousand Eight Hundred Sixty Seven and Thirty Two Paise Only
14	348.90	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	67.32	Rupees Sixty Seven and Thirty Two Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92
26/12

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....( )
ಶಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore